	A.W 8%=		317.84						
	Total		4290.84						
	2nd A'main		2	103.00	1.10	0.15	33.99		
	2nd A'main		1	103.00	4.00	0.15	61.80		
		Cum					95.79	4290.84	411019.56
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaiton.(Page No.17, Item No.4.31)								
	Basic Rate=		251.00						
	Add A.W.8%=		20.08						
	Total=		271.08						
	2nd A'main	2	4	103.00		0.60	494.40		
		sqm					494.40	271.08	134021.95
7	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed cement concrete for beams,columns, staircase and roof with M20 RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) (Page No.19 Item No. 4.49.1)								
	Basic Rate=		5989.00						
	Add A.W.8%=		479.12						
	Total=		6468.12						
	Bedslab								
	2nd A'main	1	2	103.00	1.00	0.15	30.90		
	Side wall								
	2nd A'main	2	2	103.00	0.15	0.60	37.08		
						Total	67.98		
	cc road 2nd A main	1	1	103.00	4.00	0.10	41.20		
							109.18		
		cum					109.18	6468.12	706189.34
8	KSRB 4.9.2 : Providing **T.M.T steel reinforcement for Bars Fe 415 R.C.C** work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3(Page No.19 Item No. 4.46.1)								
	Basic Rate=		6834.00						
	Add A.W.8%=		546.72						
	Total=		7380.72						
	qty 65kg/cum	72.60cumX65kg/cum					44.19		
		qtl					44.19	7380.72	326131.87
9	Providing and fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing and techncial specification complete as per specification (Page No.251, Item No. 31.3)								326154.01
	Basic Rate=		127.00						
	Add A.W.8%=		10.16						
	Total=		137.16						
	2nd A'main		1	8.00	4.00		32.00		
		mtr					32.00	137.16	4389.12
10	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floatyer clubbed with floting disc including cost of generator,HOM of machinery,Screed Vibratory,power Floater,blade and disc et., with all lead and lift. (Page No.190, Item No. 22.7)								
	Basic Rate=		85.00						
	Add A.W.8%=		6.80						